

TRANSNET



delivering freight reliably

TENDER NOTICE

M-2123421-640

TRANSNET CAPITAL PROJECTS

Transnet SOC Ltd invites tenders for:

The Refurbishment of Pump and Foam Stations including associated works at Island View, Port of Durban

Tenderers should have a CIDB Contractor grading of 7ME or 7SF or higher.

The physical address for collection of tender documents is:

***Transnet Capital Projects
Procurement and Contracts Department
First Floor
Queens Warehouse
237 Mahatma Gandhi Road, Durban
KwaZulu Natal***

Documents may be collected during normal working hours on Tuesday, 28 July 2015; 13h00 until, Monday 3 August 2015, 15h00.

The supply of valve products and actuators is a designated sector as per the Department of Trade and Industry (DTI), and therefore the tenderer is required to achieve a stipulated minimum threshold of 70% for Local Production and Content to be eligible to tender.

Queries relating to the issue of these documents may be addressed to:

***Snegugu Nhlapho
Telephone No.: 031 361 1271***

A compulsory Clarification Meeting with representatives of the Employer will take place at:

***Queens Warehouse
237 Mahatma Gandhi Road, Durban
On Tuesday, 4 August 2015 at 10h00 hrs.***

Please note: This document will be available at a non-refundable amount of **R500.00** each/per set (VAT included) and **all copies will be controlled and registered.** Responses other than those submitted against a controlled issued tender document, will be disqualified.

Payment is to be made into Transnet SOC Ltd, Transnet Capital Projects bank account at Standard Bank, Carlton Centre, Branch No. 002305, Account No. 001265741, Reference Tender number: 2123421-640.

An official bank deposit slip or EFT statement must be presented when collecting the document.

NO CASH PAYMENTS WILL BE ACCEPTED.

The closing time for receipt of tenders is:

*12h00 on Tuesday, 18 August 2015
Tender Box
Lift foyer of the 26th Floor,
Carlton Centre Office Block (TCP)
150 Commissioner Street,
Johannesburg.*

Telephonic, telegraphic, facsimile, emailed and late tenders will not be accepted.

Requirements for sealing, addressing, delivery, opening and assessment of tenders are stated in the Tender Data.



freight rail engineering pipelines port terminals national ports authority



Facebook.com/Transnet SOC Ltd



@follow_transnet

www.transnet.net

EXECUTIVE SUMMARY

The *works* that the *Contractor* is to perform include refurbishment of foam and pump stations and all associated works at Island View, Port of Durban. The site is accessed via Bayhead Road or Iran Road from The Bluff.

The scope of the *works* may be summarized as including the following equipment and all miscellaneous items.

- Removal of all pipework and fittings within the foam and pump stations (Pump station No. 1, Pump station No. 2, Foam Station No. 1, Foam Station No. 2).
- Refurbishment / replacement of all control valves within the pump and foam stations.
- Relocation of sub-station from inside Foam Station No. 1 to outside as shown on the drawing.
- Removal of existing diesel engine foam pump drives for foam station 2 and deliver at TNPA stores at 1 Kuwait Road in Fynlands.
- Installation of new pipework and fittings (supply, install and protect) in the pump and foam stations.
- Supply and installation of new foam pumps (electric motor driven) in foam station 1.
- Supply and installation of new electric motors and gearboxes connected to existing foam pumps in foam station 2.
- Installation of actuated valves in the foam stations 1 and 2.
- Reinstatement of all instrumentation to new piping and pumps.
- The emptying and transport of foam for one leaking foam tank as well as the tanks to be relined (client to supply transport tanker and pump).
- The re-lining of Foam Tanks A & B at Berth 8.
- The re-filling of Foam Tanks A & B at Berth 8 (TNPA to supply foam).
- Provide access and inspection points for the CCTV inspection of the piping between the pump and foam station 2 as well as the piping up until the ring main. (CCTV Inspections to be done by others)
- The replacement of 15m of piping between the pump and foam station 2.
- The inspection and repair of the leaking foam tank at Berth 1.

The *Contractor* shall supply all necessary materials, labor, tools, plant, PPE, demarcating signage and transport required for the proper completion of the works.

The *works* are to be carried out in a working harbor and in an area classified as environmentally sensitive.

Access to Island View is along Wharfside Road and from The Bluff via Iran Road. The *Contractor* notes that both roads carry a high proportion of heavy vehicle traffic serving the Southern Durban port precinct with traffic congestion especially at peak times.